M. ROMERO'S ROOFING & INSPECTIONS, INC.

TPO Material Takeoff — 9139 NE 10th Ave, Miami Shores, FL

Single-family residence · GAF EverGuard TPO 60 mil smooth white, MECHANICALLY ATTACHED to plywood (NOA 25-0707.01, System E(4)) · Rev 1, 10/20/2026

1. Measurements

Measurement	Value	Source
Field (flat), 6 planes	4,628 SF (46.3 SQ)	Draft takeoff 10/12 (scaled A-05)
Parapet wrap + Roof D fascia	~1,530 SF	Draft takeoff
Total membrane surface	~6,160 SF (61.6 SQ)	Draft takeoff
Parapet / coping	~327 LF (89 exterior + 238 interior step walls)	Draft takeoff
Deck / system	Existing 5/8" CDX plywood (deck and parapet walls) on WOOD trusses · TPO mech. attached, no insulation	Marc 10/20/2026
Parapet finish	Option 2 — TPO full wrap over wood nailer + metal coping	Client selection

2. Material Takeoff (waste included)

Material	Product / SKU	Qty	Unit	Unit $	Ext. $
TPO membrane — field	GAF EverGuard TPO .060 white 5'x100' #7561920	13	Roll	$380.00	$4,940.00
TPO membrane — parapet wrap & fascia	GAF EverGuard TPO .060 white 5'x100'	4	Roll	$380.00	$1,520.00
Detail membrane (end dams, details)	GAF TPO UN-55 24"x50' #7624920TP	1	Roll	$360.00	$360.00
Bonding adhesive (walls, tops, fascia)	GAF #1121 solvent bond adh 5 gal #77800OM	5	Pail	$170.00	$850.00
T-joint patches	GAF TPO T-joint patch 4"x4" #7712920	100	EA	$0.82	$82.00
Seam cleaner	GAF TPO seam cleaner 1 gal [7793]	1	Can	$36.65	$36.65
Termination bar (Roof D fascia)	OMG flat alum term bar 10' #FLATB06	3	PC	$8.00	$24.00
Wood nailer at parapet tops	2x8x10 (confirm PT and width 8–9")	36	EA	$10.85	$390.60
Brushes 4"	Brush 4	6	EA	$1.47	$8.82
Roller frames 9" HD	C&R; 9" HD roller frame #RF9HDN1	4	EA	$2.70	$10.80
Roller covers 9" 3/4" nap	C&R; 9" roller cover #RC9-3/4	12	EA	$1.65	$19.80
Drill-Tec #14 1.75" fasteners (E(4)) — Marc to price	~2,500	TBD			
Drill-Tec 2-3/4" Barbed SXHD plates — Marc to price	~2,500	TBD			
Metal coping cap, prefinished Kynar (Worldly Gray)	~360 LF	TBD			
Continuous coping cleats, both faces	~720 LF	TBD			
Coping miters / tees / end caps / splice plates	~20 / 6 / 12 / 36	TBD			
Preformed inside / outside corners	~25 / ~8	TBD			
TPO cut-edge sealant	10 pints	TBD			
TPO-coated metal drip edge (GAF EverGuard TPO-coated metal), gutter + open eaves	~255 LF (135 + 120) + cleats	TBD			
Nailer fasteners to steel top track (self-tapping)	~500	TBD			

Material	Product / SKU	Qty	Unit	Unit $	Ext. $
Pipe boots / curbs	None shown on A-05 — allowance	TBD			
VersaShield Solo slip sheet (only if fire rating requires)	~5,100 SF	TBD			
Gutters (~124 LF) + 7 downspouts	By others? confirm	TBD			

	Amount
Material subtotal (priced lines)	$8,242.67
Sales tax (7%)	$576.99
TOTAL MATERIAL (priced lines)	**$8,819.66**

3. Items to Confirm

- **Coping cap (client requested price):** ~360 LF prefinished Kynar coping (Worldly Gray, closest standard Kynar), sloped to roof, drips both faces, ~720 LF continuous cleats, ~20 miters / 6 tees / 12 end caps / ~36 splice plates. RAS 111 gauge and cleat spacing. Sheet-metal quote needed; not in total.
- **Drip edge in TPO-coated metal (Marc 10/20):** ~255 LF at gutter and open eaves, so the membrane heat-welds directly to the flange (no cover tape or primer). Price from Gulfeagle/fabricator; not in total.
- **Fasteners and plates (Marc pricing):** NOA 25-0707.01 E(4): Drill-Tec #14 1.75" fasteners + 2-3/4" Barbed SXHD plates at 12" o.c., rows 48" o.c., ~2,500 each incl. perimeter/corner and base-of-wall securement. Not in total until priced.
- **Deck and trusses (confirmed by Marc 10/20):** existing 5/8" CDX plywood on the deck and parapet walls, over WOOD trusses, which matches NOA E(3)/E(4). Fasteners need at least 1" embedment into the trusses. No parapet sheathing needed.
- **Wind pressures:** confirm the roof Zone 1/2/3 design pressures per code. NOA E(4) is limited to -75 psf (E(3): -60 psf at 12" o.c., -67.5 psf at 6" o.c.). If any zone exceeds -75 psf (for example -90 psf), E(4) does not qualify and the system or attachment must change.
- **Geometry:** A-05 has no overall dimensions; all quantities were scaled. Field-verify before ordering, especially coping.

Prices: M. Romero price book (Gulfeagle invoices 2/4, 2/5, 3/30/2026; shop list 6/26/2026). Quantities from the 10/12/2026 draft takeoff (scaled from A-05, A-03, S-05, S-06). TBD lines are NOT in the total. Field verification required.