M. ROMERO'S ROOFING & INSPECTIONS, INC.

Roof Plan Summary — 9730 E Indigo St, Miami, FL 33157

Indigo Land LLC Dialysis Clinic · Source: Sheet S-4.0 Roof & Parapet Plan (Proj. 2026024, issued 05-28-2026) · Prepared 10/19/2026

1. Main Roof (inside parapets)

Item	Value	Source
Building (outside)	**35'-0" x 102'-2"**	Printed
Roof field (inside parapets)	**33'-8" x 100'-10" = 3,395 SF (34.0 SQ)**	Printed dims
Deck	6" concrete slab, top 33.25' NGVD (flat)	Printed
Slope	1/4" per ft to west by tapered insulation; crickets between scuppers	Plan
Drainage	3 scuppers, west parapet; S.S. collector head + 4"x4" downspout each	Plan / Det. 3
Parapets	8" CMU, (1)#5 @ 32" o.c., 3'-0" high, all 4 sides	Printed
Base flashing (parapet inside)	**269 LF**	Calculated
Coping (centerline)	**~272 LF**	Calculated
Penetrations / RTUs	None shown on S-4.0	Confirm w/ M-P

2. Concrete Canopy / Eyebrow Slab (north & west, outside parapet) — provisional

Piece	Size	Quantity
North strip	44'-0" x ~5'-2"	~229 SF
West, wide part	9'-0" x ~18'-10"	~169 SF
West, narrow strip	~3'-0" x ~83'-4"	~250 SF
Total canopy		**~648 SF (6.5 SQ)**
Drip edge (outer edges)		~166 LF
Canopy-to-parapet wall flashing		~137 LF

3. Roof System & Details (Dets. 2, 3, 4 — NTS)

Component	Specification
Membrane	3-ply mod-bit: mech. attached base sheet + interply sheet + torch-applied granulated cap sheet (Preset F1 / L4)
Insulation	Rigid tapered insulation, mechanically attached to structural deck
Perimeter	6' perimeter at 1/2":12 beyond 16 ga ARBS: first 2' LWIC only, then 2' of 1" board, then 2' additional 2" board
Cant	A.R.B.S. cant strip, 5", 16 ga galv. steel, 1/4" x 1-1/4" drive pins @ 12" o.c.
Base flashing	8" min. at parapet (Det. 4); fire-rated granulated cap flashing
Termination	Flat term bar 1/4" x 1-1/4" S.S. Z-Mac; cap sheet under coping onto T.O. parapet, min. 6" overlap
Coping	22 ga continuous S.S. coping cap, 1:12 slope, over A.R.B.S. 16 ga galv. blocking cleat @ 8" o.c. (#14 x 1-1/4" pins, 1" from ends); S.S. drive pins @ 12" o.c.; asphalt primer
Scuppers	24 ga S.S. escutcheon, membrane picture-framed through wall; overflow scuppers min. 12" W x 6" H; inlet 2" min / 4" max above low point
Collector / downspout	22 ga S.S. collector head; 4"x4" 22 ga S.S. downspout (30 gpm); 18 ga S.S. brackets @ 30" o.c.
Canopy edge	Low-profile drip edge 4"x3" min.; new torch cap over interply over mech. attached modified base sheet
Attachments	Calculated to current FBC wind zones; shop drawings to Bldg. Dept. for approval

4. Conflicts to Resolve

- **Insulation:** Det. 4 calls new LWIC; Dets. 2-3 call rigid tapered board.
- **Overflow scuppers:** details say "see plan"; plan shows none.
- **Base flashing height:** 6" min (Dets. 2-3) vs 8" min (Det. 4). Recommend 8".
- **Canopy:** north depth not dimensioned; confirm canopy receives the new roof system (shown in Det. 3).

5. Critical Missing Data for Miami-Dade Permitting

- Wind design data, Risk/Exposure Category, Zone 1/2/3 pressures
- Mean roof height (roof slab 33.25' NGVD; grade not given)
- NOA numbers: mod-bit system, insulation, LWIC
- Mod-bit product selection: base, interply, cap
- Tapered insulation / cricket layout (supplier)
- Penetrations and RTUs (mechanical / plumbing sheets)

Notes: Main roof quantities from printed dimensions. Canopy north depth scaled (not dimensioned) and marked provisional. PDF plots ~2.5% under the stated 3/16" = 1'-0" scale; scaled values corrected to printed dimensions. Only sheet S-4.0 reviewed; field verification required.