M. ROMERO'S ROOFING & INSPECTIONS, INC.

Mod-Bit Material Takeoff — 9730 E Indigo St, Miami, FL 33157

Indigo Land LLC dialysis clinic · Primed concrete deck · 1/4" tapered ISO to scuppers · GAF StrataVent + Ruberoid 20 smooth + granulated cap · Rev 1, 10/20/2026

1. Measurements

Measurement	Value	Source
Roof field inside parapets	33'-8" x 100'-10" = 3,394.7 SF (33.95 SQ)	S-4.0 printed dims
Deck	6" concrete slab, flat (33.25' NGVD); primed	S-4.0 / Marc 10/20
Slope	1/4"/ft tapered ISO to the 3 west scuppers, crickets between	S-4.0 / Marc 10/20
Parapet base (cant, flashing, term bar, counterflashing)	269.0 LF	S-4.0
Parapet height	1.5' (Marc 10/20) — S-4.0 shows 3'-0"	CONFIRM
Wall flashing area	269 LF x 2.0' (1.5' wall + 6" onto field) = 538 SF (5.38 SQ)	Calc
Coping centerline (option)	~271.7 LF	S-4.0
Tapered ISO (Gulfeagle #26-2928)	33.24 SQ tapered + 2.00 SQ crickets; 0.5" start, 8.94" max; X/Y panels over 2"/4"/6"/8" ISO fill, crickets to 3 scuppers	Supplier quote + layout 10/19/26
Waste	10% sheets, metals, accessories (ISO per supplier)	Price-book rule

2. Material Takeoff — Base Bid (waste included)

Material	Product / SKU	Qty	Unit	Unit $	Ext. $
Concrete deck primer	Tropical 410 asphalt primer 5 gal	8	Pail	$43.48	$347.84
Tapered ISO system 1/4"/ft + 1/2" crickets	Gulfeagle tapered quote #26-2928 (10/19/26)	1	LS	$10,387.00	$10,387.00
Interply / base flashing ply	GAF Ruberoid 20 smooth 1.5 SQ	29	Roll	$85.00	$2,465.00
Granulated cap sheet (field + flashing)	GAF Capsheet 1.25 SQ (granulated)	35	Roll	$59.90	$2,096.50
Hot asphalt (if hot-mopped)	Asphalt (price book: 'Asphalt (24)')	59	Keg	$40.00	$2,360.00
Cant strip	Cant strip 1x4 (84 LF/unit)	4	EA	$40.00	$160.00
Termination bar	OMG flat alum term bar 10' #FLATB06	30	PC	$8.00	$240.00
Counterflashing (surface-mount)	Stucco stop 5" 26 ga galv 10'	30	PC	$8.15	$244.50
Masonry anchors	OMG 1/4"x1-1/4" masonry anchor #MA114X	6	Box	$9.00	$54.00
Flashing cement (term bar seal)	Tropical 2100 Rubberoid flashing cement	25	Tube	$6.15	$153.75
Sealant (top of counterflashing)	Bostik 915 white caulking	25	Tube	$4.90	$122.50
Granules (touch-up)	Granule bags	2	Bag	$19.80	$39.60
Mops	Mop	6	EA	$7.15	$42.90
Brushes 4"	Brush 4	6	EA	$1.47	$8.82
GAF StrataVent venting base sheet ($59.00/roll shop list)	37.3 SQ needed (33.95 + 10%) — roll coverage not in price book	TBD			
Cover board / overlay (if NOA requires)	Not in Gulfeagle quote — 33.95 SQ	TBD			
6' perimeter @ 1/2":12 w/ LWIC + 1"/2" board (S-4.0 det. 2–4)	Not in Gulfeagle quote — confirm scope	TBD			
Scuppers (3 primary + overflow, 12"x6" min) + 24 ga S.S. escutcheons	Overflow count not on plan	TBD			
22 ga S.S. collector heads + 4"x4" downspouts	3 each	TBD			

Material	Product / SKU	Qty	Unit	Unit $	Ext. $
Canopy / eyebrow slab (~648 SF)	Excluded — option: liquid-applied (GAF/Tremco/Sika)	TBD			

	Amount
Material subtotal (priced lines)	$18,722.41
Sales tax (7%)	$1,310.57
TOTAL MATERIAL — BASE (priced lines)	**$20,032.98**

3. Option / Add Alternate (not in base total)

Option / add alternate	Product	Qty	Unit	Unit $	Ext. $
Wood nailer at parapet top	2x8x10 (confirm PT / width)	30	EA	$10.85	$325.50
22 ga continuous S.S. coping cap + A.R.B.S./cleat	Per S-4.0 det. 2–4	TBD	LF	TBD	Quote

Option priced lines: $325.50 + tax $22.79 = **$348.29** (nailer only; coping by sheet-metal quote).

4. Items to Confirm

- **Application method:** quantities assume HOT-MOPPED plies (Ruberoid 20 smooth and granulated cap are mop/cold-adhesive sheets). S-4.0 details call for a mechanically attached base and TORCH cap. If the architect requires torch, swap to torch-grade ply/cap and delete asphalt/mops. Pending reply to the hot-mop vs torch email.
- **StrataVent placement:** StrataVent is a venting base sheet usually spot-mopped to the deck. Over tapered ISO, confirm the sequence (deck primer → ISO in asphalt → StrataVent?) or whether StrataVent goes directly on the primed slab with ISO above. Affects asphalt quantity and NOA compliance.
- **Parapet height vs taper:** at the east high side the ISO is 8.94" plus ~0.5" of plies, so a 1.5' (18") parapet leaves only ~8.5" above the finished roof. That is just enough for the 8" min base flashing, with almost no room for term bar + counterflashing below the coping. Confirm parapet height (1.5' per Marc vs 3'-0" on S-4.0). Flashing quantities use 1.5'. At 3'-0" the wall flashing adds ~400 SF (≈ 4 more Ruberoid 20 rolls and 4 more cap rolls).
- **Tapered ISO (Gulfeagle #26-2928, $10,387, expires 11/18/2026):** the quote area is 33.24 SQ vs 33.95 SQ measured inside the parapets (~71 SF short, 2%), so have Gulfeagle confirm the 33'-8" x 100'-10" field. Base layer and overlay are not included. Up to 5 layers at the east side (8" fill + taper). The asphalt line assumes every ISO layer is hot-mopped (99.24 SQ applied). If the bottom layer is mechanically fastened or foam-adhered, asphalt drops ~9 kegs per 33 SQ layer and fasteners/adhesive are added. S-4.0 det. 2–4 also call for a 6' perimeter at 1/2":12 with LWIC/1" and 2" board, and detail 4 mentions LWIC. Confirm the insulation scope with the architect; a cover board may be required by the NOA.
- **Scuppers:** 3 primary shown; overflow scuppers (min 12" x 6") are required but the count is not on the plan. Collector heads and 4"x4" 22 ga S.S. downspouts are a sheet-metal quote.
- **Canopy / eyebrow (~648 SF, provisional):** not in this takeoff. Detail 3 shows a mod-bit system on it; the architect email proposed a liquid-applied alternate.
- **Option — wood nailer + coping:** FBC/RAS 111 require edge metal and coping to be fastened to wood nailers or to an NOA-approved system (S-4.0 shows A.R.B.S. cleats). Nailer anchorage to CMU (Tapcons/wedge anchors) and the 22 ga S.S. coping are not priced.
- **Critical Missing Data for Miami-Dade Permitting:** wind design data and Zone 1/2/3 pressures; mean roof height; NOA numbers for the mod-bit system, insulation and LWIC; penetrations/RTUs (M/P sheets).

Prices: M. Romero price book (shop list 6/26/2026; Gulfeagle invoices 2/4, 2/5, 3/30/2026). Quantities from S-4.0 (Roof & Parapet Plan, 05-28-2026). TBD lines are NOT in the total. Field verification required.