M. ROMERO'S ROOFING & INSPECTIONS, INC.

TPO Material Takeoff — 769 NE 74th St, Miami, FL

Single-family residence · City of Miami approved BD23009481001 (4/1/2025) · GAF EverGuard TPO .060 FULLY BONDED over 1/4" tapered ISO · Rev 0, 10/20/2026

1. Measurements

Measurement	Value	Source
Flat roof (TPO field)	2,328.42 SF	Bluebeam, A-3
Top slab for waterproofing	111.44 SF	Bluebeam, A-3 (included in TPO field)
Total membrane area	**2,439.86 SF (24.4 SQ)**	
Parapet, inside	262.45 LF	Bluebeam, A-3
Parapet height	~1'-4" (T.O. slab 33.67' / parapet 35.00' NGVD)	A-3 roof detail
Drain points	4 (scuppers / overflow) — verify	Gulfeagle 25-1454-V3 drawing
Tapered ISO	23.37 SQ, 1/4"/ft, 5.50" min to 11.81" max, LTTR 49.66	Gulfeagle 25-1454-V3

2. Material Takeoff (waste included)

Material	SKU / Product	Order	Unit	Unit $	Ext. $
Field membrane	GAF TPO .060 white 5'x100' #7561920	6	Roll	$380.00	$2,280.00
Bonding adhesive — field	GAF #1121 solvent bond adh 5 gal #77800OM	9	Pail	$170.00	$1,530.00
Bonding adhesive — flashings	GAF #1121 5 gal	2	Pail	$170.00	$340.00
Detail / wall flashing	GAF TPO UN-55 24"x50' #7624920TP	6	Roll	$360.00	$2,160.00
Seam cleaner	GAF TPO seam cleaner 1 gal [7793]	1	Can	$36.65	$36.65
T-joint patches	GAF TPO T-joint patch 4"x4" #7712920	24	EA	$0.82	$19.68
Water Block	GAF EverGuard Water Block 10.3 oz #8008	19	Tube	$8.50	$161.50
FlexSeal	GAF TopCoat FlexSeal #8962920WP	25	Tube	$14.00	$350.00
Termination bar	OMG flat alum term bar 10' #FLATB06	29	PC	$8.00	$232.00
Masonry anchors (term bar @ 6")	OMG 1/4"x1-1/4" masonry anchor #MA114X	6	Box	$9.00	$54.00
Tapered ISO insulation	GAF EnergyGuard tapered ISO — Gulfeagle quote	1	Lump	$11,971.00	$11,971.00
Two-part stainless reglet + counterflashing (262 LF)	Per A-3 — not in price book	TBD			
Insulation adhesive (ISO to concrete)	Per NOA	TBD			
Pipe boots / CU stand supports	Count from M/P sheets	TBD			

	Amount
Material subtotal	$19,134.83
Sales tax (7%)	$1,339.44
TOTAL MATERIAL COST	**$20,474.27**

3. Items to Confirm

- **8" min. base flashing (Marc, 10/20):** parapet is ~16" above the slab, so exposure is ~10.5" at the 5.5" low points (OK) but only ~4.2" at the 11.81" high points (short ~3.8"). Fix with the architect and Gulfeagle: raise the parapets ~4" at the high sides, redesign the taper (thinner base layers; check R-value), or add drains/crickets.
- **Gulfeagle quote expired:** 25-1454-V3 ($11,971) was dated 7/16/2025 and expired 7/30/2025. Requote before pricing. The quote is labeled "NW 74th St"; its area matches this job.
- **Attachment:** plan details say "TPO fastened to rigid insulation as per manufacturer spec". The system priced here is GAF TPO FULLY BONDED per Marc. Confirm the NOA covers adhered ISO on a concrete deck.
- **Penetrations:** CU-1 to CU-3 sit on a metal stand. Stand legs, pipe boots and any curbs are not counted yet.

Prices: Gulfeagle invoices 2/4, 2/5 and 3/30/2026 (price book). Water Block / FlexSeal quantities are bead-size estimates. TBD items are not in the total. Field verification required.