M. ROMERO'S ROOFING & INSPECTIONS, INC.

TPO Material Takeoff — 769 NE 74th St, Miami, FL

Single-family residence · City of Miami approved BD23009481001 (4/1/2025) · GAF EverGuard TPO .060 FULLY BONDED over 1/4" tapered ISO · Rev 2, 10/20/2026 · Flashing per GAF details 301A + 307A

1. Measurements

Measurement	Value	Source
Flat roof (TPO field)	2,328.42 SF	Bluebeam, A-3
Top slab for waterproofing	111.44 SF	Bluebeam, A-3 (included in TPO field)
Total membrane area	**2,439.86 SF (24.4 SQ)**	
Parapet, inside	262.45 LF	Bluebeam, A-3
Parapet height	~1'-4" (T.O. slab 33.67' / parapet 35.00' NGVD)	A-3 roof detail
Drain points	4 (scuppers / overflow) — verify	Gulfeagle 25-1454-V3 drawing
Tapered ISO	23.37 SQ, 1/4"/ft, 5.50" min to 11.81" max, LTTR 49.66	Gulfeagle 25-1454-V3

2. Material Takeoff (waste included)

Material	SKU / Product	Order	Unit	Unit $	Ext. $
TPO membrane (field + wall strips)	GAF EverGuard TPO .060 white 5'x100' #7561920	7	Roll	$380.00	$2,660.00
Detail membrane (corners/details)	GAF TPO UN-55 24"x50' #7624920TP	1	Roll	$360.00	$360.00
Bonding adhesive	GAF #1121 solvent bond adh 5 gal #77800OM	11	Pail	$170.00	$1,870.00
Insulation adhesive	OlyBond 500	3	EA	$1,080.00	$3,240.00
Tapered ISO insulation	GAF EnergyGuard tapered ISO — Gulfeagle revised quote	1	Lump	$12,929.00	$12,929.00
Termination bar (2 rows)	OMG flat alum term bar 10' #FLATB06	60	PC	$8.00	$480.00
Masonry anchors	OMG 1/4"x1-1/4" masonry anchor #MA114X	9	Box	$9.00	$81.00
Counterflashing (surface-mount)	Stucco stop 5" 26 ga galv 10'	29	PC	$8.15	$236.35
Water Block	GAF EverGuard Water Block 10.3 oz #8008	22	Tube	$8.50	$187.00
FlexSeal caulk-grade sealant	GAF TopCoat FlexSeal #8962920WP	30	Tube	$14.00	$420.00
Seam cleaner	GAF TPO seam cleaner 1 gal [7793]	2	Can	$36.65	$73.30
T-joint patches	GAF TPO T-joint patch 4"x4" #7712920	24	EA	$0.82	$19.68
Brushes 4"	Brush 4	6	EA	$1.47	$8.82
Drill bits (masonry)	Drill bits	6	EA	$2.64	$15.84
Roller frames 9" HD	C&R; 9" heavy duty roller frame #RF9HDN1	4	EA	$2.70	$10.80
Roller covers 9" 3/4" nap	C&R; 9" roller cover 3/4" nap #RC9-3/4	12	EA	$1.65	$19.80
Mops	Mop	2	EA	$7.15	$14.30
ALT: two-part SS reglet in lieu of stucco stop	A-3 spec — price TBD	TBD			
Pipe boots / CU stand supports	Count from M/P sheets	TBD			

	Amount
Material subtotal	$22,625.89
Sales tax (7%)	$1,583.81
TOTAL MATERIAL COST	**$24,209.70**

3. Items to Confirm

- **8" min. base flashing (Marc, 10/20):** parapet is ~16" above the slab, so exposure is ~10.5" at the 5.5" low points (OK) but only ~4.2" at the 11.81" high points (short ~3.8"). Fix with the architect and Gulfeagle: raise the parapets ~4" at the high sides, redesign the taper (thinner base layers; check R-value), or add drains/crickets.
- **Tapered ISO:** revised Gulfeagle proposal $12,929 (per Marc, 10/20/2026) replaces the expired 25-1454-V3 ($11,971). Confirm the revised design addresses the 8" min. flashing at the high points.
- **Wall flashing (GAF 301A + 307A):** reinforced EverGuard TPO strips (30") up the parapet, 8" min. height; term bar at the base of the wall (307A) and at the top (301A), 12" o.c., Water Block behind and FlexSeal on top; surface-mount counterflashing over it. UN-55 for corners and details only.
- **Attachment:** plan details say "TPO fastened to rigid insulation as per manufacturer spec". The system priced here is GAF TPO FULLY BONDED per Marc. Confirm the NOA covers adhered ISO on a concrete deck.
- **Penetrations:** CU-1 to CU-3 sit on a metal stand. Stand legs, pipe boots and any curbs are not counted yet.

Prices: Gulfeagle invoices 2/4, 2/5 and 3/30/2026 (price book). Water Block / FlexSeal quantities are bead-size estimates. TBD items are not in the total. Field verification required.