M. ROMERO'S ROOFING & INSPECTIONS, INC.

# TPO Material Takeoff — 9139 NE 10th Ave, Miami Shores, FL

Single-family residence · GAF EverGuard TPO 60 mil smooth white, MECHANICALLY ATTACHED to plywood (NOA 25-0707.01, System E(4)) · Rev 0, 10/20/2026

## 1. Measurements

| Measurement | Value | Source |
|---|---|---|
| Field (flat), 6 planes | 4,628 SF (46.3 SQ) | Draft takeoff 10/12 (scaled A-05) |
| Parapet wrap + Roof D fascia | ~1,530 SF | Draft takeoff |
| Total membrane surface | ~6,160 SF (61.6 SQ) | Draft takeoff |
| Parapet / coping | ~327 LF (89 exterior + 238 interior step walls) | Draft takeoff |
| Deck / system | 5/8" CDX plywood on NuTruss steel trusses · TPO mech. attached, no insulation | S-06 Rev 1-9-26 |
| Parapet finish | Option 2 — TPO full wrap over wood nailer + metal coping | Client selection |

## 2. Material Takeoff (waste included)

| Material | Product / SKU | Qty | Unit | Unit $ | Ext. $ |
|---|---|---|---|---|---|
| TPO membrane — field | GAF EverGuard TPO .060 white 5'x100' #7561920 | 13 | Roll | $380.00 | $4,940.00 |
| TPO membrane — parapet wrap & fascia | GAF EverGuard TPO .060 white 5'x100' | 4 | Roll | $380.00 | $1,520.00 |
| Detail membrane (end dams, details) | GAF TPO UN-55 24"x50' #7624920TP | 1 | Roll | $360.00 | $360.00 |
| Fasteners (E(4) field + perimeter + base of wall) | PROXY: Trufast #14 HD 3" #HD-3000 (1M/bkt) | 3 | Bkt | $133.00 | $399.00 |
| Plates | PROXY: GAF 2-3/8" Drill-Tec barbed plate #8678 (1M/bkt) | 3 | Bkt | $350.00 | $1,050.00 |
| Bonding adhesive (walls, tops, fascia) | GAF #1121 solvent bond adh 5 gal #77800OM | 5 | Pail | $170.00 | $850.00 |
| T-joint patches | GAF TPO T-joint patch 4"x4" #7712920 | 100 | EA | $0.82 | $82.00 |
| Seam cleaner | GAF TPO seam cleaner 1 gal [7793] | 1 | Can | $36.65 | $36.65 |
| Cover tape over drip-edge flanges | GAF TPO 6"x100' cover tape #755A920 | 3 | Roll | $290.02 | $870.06 |
| Termination bar (Roof D fascia) | OMG flat alum term bar 10' #FLATB06 | 3 | PC | $8.00 | $24.00 |
| Wood nailer at parapet tops | 2x8x10 (confirm PT and width 8–9") | 36 | EA | $10.85 | $390.60 |
| Parapet roof-side sheathing | Plywood 4x8 (or DensDeck Prime — price TBD) | 33 | Sheet | $24.80 | $818.40 |
| Drip edge (gutter eaves + open eaves) | PROXY: 3x3 Brown 10' (Kynar Urbane Bronze / Worldly Gray TBD) | 26 | PC | $6.50 | $169.00 |
| Brushes 4" | Brush 4 | 6 | EA | $1.47 | $8.82 |
| Roller frames 9" HD | C&R; 9" HD roller frame #RF9HDN1 | 4 | EA | $2.70 | $10.80 |
| Roller covers 9" 3/4" nap | C&R; 9" roller cover #RC9-3/4 | 12 | EA | $1.65 | $19.80 |
| Metal coping cap, prefinished Kynar (Worldly Gray) | ~360 LF | TBD | | | |
| Continuous coping cleats, both faces | ~720 LF | TBD | | | |
| Coping miters / tees / end caps / splice plates | ~20 / 6 / 12 / 36 | TBD | | | |
| Preformed inside / outside corners | ~25 / ~8 | TBD | | | |
| TPO cut-edge sealant | 10 pints | TBD | | | |

| Material | Product / SKU | Qty | Unit | Unit $ | Ext. $ |
|---|---|---|---|---|---|
| TPO primer | 1 gal | TBD | | | |
| Nailer fasteners to steel top track (self-tapping) | ~500 | TBD | | | |
| Pipe boots / curbs | None shown on A-05 — allowance | TBD | | | |
| VersaShield Solo slip sheet (only if fire rating requires) | ~5,100 SF | TBD | | | |
| Gutters (~124 LF) + 7 downspouts | By others? confirm | TBD | | | |

| | Amount |
|---|---|
| Material subtotal (priced lines) | $11,549.13 |
| Sales tax (7%) | $808.44 |
| **TOTAL MATERIAL (priced lines)** | **$12,357.57** |

## 3. Items to Confirm

- **Coping not priced:** ~360 LF of prefinished Kynar coping + cleats + accessories is the largest open item. Get a sheet-metal quote (color Worldly Gray, match closest standard Kynar).
- **Fasteners/plates are proxies:** NOA 25-0707.01 E(4) calls for Drill-Tec #14 1.75" + 2-3/4" Barbed SXHD plates. Priced here with Trufast HD 3" / GAF 2-3/8" barbed plates from the price book. Reprice once Gulfeagle quotes the E(4) parts.
- **Steel trusses vs. NOA:** E(3)/E(4) assume wood trusses with 1" embedment. A GAF technical letter or an engineer's RAS 117 fastening design is needed before permit.
- **Deck:** confirm 5/8" CDX plywood (S-06) vs. ZIP System (finish-options sheet). S-05 still shows a metal deck, DensDeck and fully adhered TPO; confirm S-06 governs.
- **Wind pressures:** Zone 1/2/3 design pressures are not on the sheets. They must be no higher than -75 psf for E(4).
- **Geometry:** A-05 has no overall dimensions; all quantities were scaled. Field-verify before ordering, especially coping.
- **Parapet sheathing:** 33 sheets priced as plywood. Confirm whether the framer or roofer provides it, and plywood vs. DensDeck.

Prices: M. Romero price book (Gulfeagle invoices 2/4, 2/5, 3/30/2026; shop list 6/26/2026). Quantities from the 10/12/2026 draft takeoff (scaled from A-05, A-03, S-05, S-06). TBD lines are NOT in the total. Field verification required.