M. ROMERO'S ROOFING & INSPECTIONS, INC.

Material List — 5340 Riviera Dr, Coral Gables, FL 33146

Rev 0 · October 14, 2026 · All quantities include waste

Tile Roof — 38.4 SQ net, 4:12 hip · Waste 15%

#	Material	Order Qty
1	Westlake Saxony 900 concrete field tile	**44.1 SQ**
2	Saxony 900 hip & ridge trim	**211 LF**
3	Eave closure	**324 LF**
4	Westlake TileSeal underlayment (direct to deck)	**23 rolls**
5	Drip edge	**33 pcs @ 10'**
6	Sidewall / L-flashing at roof monitor	**4 pcs @ 10'**
7	Tile attachment (foam/adhesive or fasteners)	TBD per NOA

Flat Roofs — 9.9 SQ · GAF TPO 60-mil fully bonded over 1/4" tapered ISO · Concrete deck

#	Material	Order Qty
1	GAF TPO .060 white 5' x 100'	**3 rolls**
2	Tapered ISO, 1/4"/ft (992 SF)	**Supplier quote**
3	GAF UN-55 detail membrane 24" x 50'	**5 rolls**
4	GAF #1121 bonding adhesive, 5 gal	**6 pails**
5	GAF TPO seam cleaner, 1 gal	**1 can**
6	Edge metal (north eyebrow)	**5 pcs @ 10'**
7	Termination bar	**7 pcs @ 10'**
8	Scupper sleeves	**5 EA**
9	Insulation adhesive (ISO to concrete)	TBD per NOA
10	Cover board (if NOA requires)	TBD per NOA
11	T-joint patches, pipe boots, curbs	Count from layout / M-P sheets

Notes: Tile ordered by SQ/LF; supplier to convert to pieces for the selected Saxony 900 profile and color. Items marked TBD depend on product approvals (NOA) and design wind pressures. Penetration items pending mechanical/plumbing sheets. Quantities are based on plans by Balli-Trautman Architects (Bid Set 10/21/2025); field verification required.